### CITY OF MOUNTAIN VIEW

SFUND RECORDS CTR 2807-91944

Application for Industrial Wastes Discharge Permit

A Ir	Address 464 E111a S Address of Point of Disc Individual Responsible for industrial waste Attach Map Showing Po	charge 545 When Signature Signature wint of Discharge	risman Rd. M regory Geary Littyon 12 e. Sampling Points,	tn. View. Ca	Telep	,3, & 4 hone <u>(415) 962</u> (408) 373	
. F	low Rate: Average	1,110,000 g	als/day Max	1.220.0091s/day	y Peak Ho	urly <u>1150</u> G	PM
. s	ubmit separate stateme	int:					
	. Detailing type of ind		e of products				
	Listing chemicals use						ور کا جو
	. Describing waste trea						
	. Giving characteristics					પ્રાત્મ સ્કૃતિ હતા છે	•
	. Concerning radioacti		,				
	. Naming organic solve		and concentration a	It point of discharge			
		<del></del>					<u> </u>
lr	ndicate the point of dis	charge concent	ration of the follow	ring characteristics a	and mass emission	rates where applic	able.
	iochemical oxygen den		10mg/1		•		
C	hemical oxygen deman	id (C.O.D.)	12 mg/1		on content pH 5.		
	otal Solids, Average		100 mg/1			5.0 mg/1	
S	uspended Solids, Avera	ige .	10 mg/1	Chlorine der	mand	5.0 mg/1	3 <b>t</b> , - 1 -
T	emperature		60°F		•		
		Max. Cone.	Allowable Mass		Max. Conc.	Allowable Mos	
·		Allowable	Emission Rate		Allowable	Emission Rate	
		mg/1	kg/dey		mg/1	kg/day	
Α	vrsenic	_0.1_	_0_01_	Formaldehyde	_5.0_	_0_5_	•
8	arium	_5.0_	_0.5_	Lead	_0.5_	-0.05	
8	eryllium	1.0	_0.1_	Manganese	1.0	-0-1-	
8	oron	_1.0_	_0.1	Mercury	-0-05	_0.005	
C	hlorine	50.0	_5.0_	Nickel	_1_0_	_0.1_	
C	admium	_0.1_	0.01	Chloroform	50-0-		
C	hromium Hexavalent	_1.0_	_0_1_	Phenois	1.0	-0.1-	
C	hromium Total	_2.0_	_0.2_	Selenium	2.0	-0.2	: '
C	obalt	_18.0	-0.1-	Silver	_5.0_	-0.5	
C	opper	_1.0_	-0.1	Zinc	_5_0_	-0.5	
C	resols	_2.0_	_0.2_				
C	yanides	-1-0-	-0.1				
TT	O BE COMPLETED BY	APPLICANT					
mit	to Discharge Industrial	Wastes in Acco	rdance with This A	pplication Approved	d Subject to	Attached Ge	neral
	helley, Director of Pub					Conditions	
natu	/* * *	, 11	.11.		9 ~ 6		
		an An	uly	Dat	• ~ 3 -0	V	*
	to Discharge Exception tails:	al Industrial Wa	este Approved				
. Del	tans.				And the second		
•							
•		* :				· · · · · · · · · · · · · · · · · · ·	
٠.							
	hallan Pinisan (A.)	, 11 - 444 - 4					
ın Si	helley, Director of Publ	lic Works					

111

(PW-23)

#### CITY: OF MOUNTAIN VIEW

#### Industrial Waste Discharge Permit

DATE: February 5, 1980 NO. 001-81-4

NAME OF ORGANIZATION: Fairchild Camera & Instrument Corporation

ADDRESS: 464 Ellis Street, Mountain View, Calif. 94043

#### GENERAL CONDITIONS

- This permit is issued under the ordinances and regulations of the City of Mountain View currently in effect, but all discharges hereunder shall comply with all ordinances and regulations of the City and all other applicable local, state, and federal regulations, whether now in effect or hereafter adopted or amended.
- 2. Any violation of the terms of this Permit or the ordinances or regulations of the City shall be grounds for revocation.
- If any proposed revisions in plant operations are expected to cause significant changes in waste water quality or quantity (25 percent or more, or 25,000 gallons per day) from that given in approved Permit information, an application for an amended permit must be submitted for approval detailing the nature of the changes.
- 4. In accordance with Section 35.32.8 of the City Code, accidental discharges of industrial wastes shall be reported immediately to the Public Works Department, telephone number 967-7211, Ext. 270, during normal office hours, or to the Fire Department, telephone number 968-4415, on holidays or after normal office hours AND to the Palo Alto Regional Water Quality Control Plant, telephone number 329-2598 so that appropriate countermeasures may be taken.
- 5. This Permit is not transferable without prior written consent of the Director of Public Works. In general, a change of ownership will require a new permit.
- 6. The issuance of this permit does not constitute a warranty that the design capacity of the sewage collection and treatment system is sufficient to accommodate peak sewage flows from all dischargers who may now or hereafter be connected to the system. Pursuant to Sec. 35.32.1(d) the City reserves the right to impose restrictions on sewage discharges where necessary in the judgment of the City to assure the proper functioning in the sewerage system.

#### SPECIFIC CONDITIONS

1.	This permit is for a period ending on April 1, 1981	if significat	it pro-
	**************************************	reducing total	l plant
	ARXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	flow and appro	oved pre-
2.	This permit applies to industrial waste discharges	treatment fac:	llities :
	the following location(s) only:	have been inst	called.

the following location(s) only:

545 Whisman Road Buildings 1, 2, 3 and 4

Your attention is called to the fact that flow rates shown on the permit application exceed per-acre design flows of the sewers serving the above locations. Restrictions or additional charges may be imposed in accordance with Sec. 35.32.1(d) of the City Code should peak sewage flows from the total upstream acreage approach the capacity of these sewers.

### APPLICATION FOR INDUSTRIAL WASTES DISCHARGE PERMIT, ITEM C.

## 1. Type of Industry and Nature of Products

Fairchild Semiconductor processes silicon metal into electronic semiconductor devices.

# 2. Chemicals used in semiconductor device processing are:

Gases	Liquids	Liquids
Nitrogen	Sulfuric acid	Methano1
Hydrogen	Nitric acid	Isoperpano1
Oxygen	Hydrofluoric acid	Methylene chloride
Argon	Hydrochloric acid	Trichloroethane
Hydrogen chloride	Acetic acid	Detergents
Chlorine	Phosphoric acid	Aluminum sulfate
Compressed air	Ammonium fluoride	Sodium carbonate
Ammonia	Ammonium hydroxide	Sodium hydroxide
	Acctone	Freon
		Glycerin
		Xylene


### 3. Waste Treatment Facilities

Neutralization of acids is provided by injection of NaOH and/or H<sub>2</sub>SO<sub>4</sub> into mixing tanks with continuous monitoring and control. Fluoride solutions are captured and disposed of separately, not into the city sewer.

4. Characteristics of exceptional industrial wastes. None.

No radioactive wastes are discharged.

Organic solvents are captured for storage and recycling.



# ADDITIONAL INFORMATION REGARDING THE I.W. PERMIT FOR BUILDING 1. 2 & 3

- (1) The LIC relocation to Building 1 will remove production at Building 20. resulting in a transfer of water flow within the Mountain View complex (not a water flow increase).
- (2) The conversion from 3" to 4" wafers by LIC will result in a 44% increase in production with no increased labor or water usage.
- (3) A BPM group will move from Building 20 to the South San Jose facility in the second quarter of 1980, eliminating the flow from this operation.
- (4) The BPM operations that remain in Mountain View will convert from 3" to 4" wafers, resulting in a 44% production increase with no increased labor or water usage.
- (5) The Transistor group will be moving to the San Rafael facility, resulting in the elimination of flow from this operation.
- (6) A 6 month feasability study will be performed on 300 gpm D.I. Water reclaim and 600 gpm treated effluent reclaim.
- (7) Pending favorable completion of the feasability studies, construction of the above reclaim systems will take an estimated 2 years (depending upon economic climate).
- (8) The projected flow rates from the new system were based on peak water usage at full production rates, actual flow rates will be less.
- (9) The relocation of LIC at Building 1 will not be fully operational until 1-2 years after start-up.
- (10) Actual flow rates can only be measured after the system is installed. Loss of water via cooling towers is known to be significant.
- (11) Planning is under way to convert to 5" wafers. This would yield a 63% production increase over todays output without increasing labor or water usage.
- (12) The vast majority of construction projects at FC & I are based on technological advances to increase yields, not new production that requires more labor or water usage.
- (13) Even without the above, the new neutralization pit would not increase our total water discharge but would tend to only balance the discharge from two locations.